Phase II hydrant replacement

395 Industrial Drive (next to front door)	\$5,970.00
310 Elm Street(plus a gate valve installation while replacing the hydrant)	Village Control of the Control of th
307 Oak Street	\$6,345.00
205 Taliaferro Drive	\$6,345.00
Corner of West Boyd & Popular Street	\$6,345.00
4541 Mountville Hogansville Road	\$6,345.00
Total	\$38,995.00

4 46,956.00 \$ 46,956.00

395 INDUSTRIAL DRIVE (NEXT TO FRONT DOOR)

Description	Quantity	Unit of Measure
HYDRANT & VALVE INSTALLATION NEW HYDRANT ASSEMBLY (TEE, VALVE & HYD) 6" DIP CL-50 6" MJ SLEEVE W/ ML CONCRETE BLOCKING GRASSING	1 10 1 1 1 TOTAL:	EA LF EA CY LS \$5,970.00



Proposal

(770) 927-0413 Office (770) 927-2533 Fax

1505 Dunlap Road, Luthersville, GA 30251

www.crawfordgrading.com

Submitted To:

Jose Vidal

City of Hogansville

waterplant@cityofhogansville.org

Date:

October 22, 2018

Job Name

Job Location

Plan Information

Valve and Hydrant Improvements

Hogansville, Ga

N/A

310 ELM STREET

Description	Quantity	Unit of Measure
HYDRANT & VALVE INSTALLATION		
SAW CUT ASPHALT	20	LF
ASPHALT DEMO	1.2	CY
TRAFFIC CONTROL	1	LS
NEW HYDRANT ASSEMBLY (TEE, VALVE & HYD)	1	EA
6" DIP CL-50	10	LF
6" MJ SLEEVE W/ ML	1	EA
CONCRETE BLOCKING	1	CY
8" GAB	5	TONS
GRASSING	. 1	LS
q	TOTAL:	\$6,345.00

307 OAK STREET

Description	Quantity	Unit of Measure
HYDRANT & VALVE INSTALLATION SAW CUT ASPHALT ASPHALT DEMO TRAFFIC CONTROL	20 1 1	LF CY LS
NEW HYDRANT ASSEMBLY (TEE, VALVE & HYD) 6" DIP CL-50 6" MJ SLEEVE W/ ML CONCRETE BLOCKING	1 10 1 1	EA LF EA CY
8" GAB GRASSING	5 1 TOTAL:	TONS LS \$6,345.00

205 TOLIAFERRO DRIVE

Description	Quantity	Unit of Measure
HYDRANT & VALVE INSTALLATION SAW CUT ASPHALT ASPHALT DEMO TRAFFIC CONTROL	20 1 1	LF CY LS
NEW HYDRANT ASSEMBLY (TEE, VALVE & HYD) 6" DIP CL-50 6" MJ SLEEVE W/ ML CONCRETE BLOCKING	1 10 1 1	EA LF EA CY
8" GAB GRASSING	5 1 TOTAL:	TONS LS \$6,345.00

CORNER OF WEST BOYD & POPLAR ST

Description	Quantity	Unit of Measure
HYDRANT & VALVE INSTALLATION SAW CUT ASPHALT ASPHALT DEMO TRAFFIC CONTROL	20 1 1	LF CY LS
NEW HYDRANT ASSEMBLY (TEE, VALVE & HYD) 6" DIP CL-50 6" MJ SLEEVE W/ ML CONCRETE BLOCKING	1 10 1 1	EA LF EA CY
8" GAB GRASSING	5 1 TOTAL:	TONS LS \$6,345.00

4541 MOUNTVILLE HOGANSVILLE ROAD

Description	Quantity	Unit of Measure
HYDRANT & VALVE INSTALLATION SAW CUT ASPHALT ASPHALT DEMO TRAFFIC CONTROL	20 1 1	LF CY LS
NEW HYDRANT ASSEMBLY (TEE, VALVE & HYD) 6" DIP CL-50 6" MJ SLEEVE W/ ML CONCRETE BLOCKING	1 10 1 1	EA LF EA CY
8" GAB GRASSING	5 1 TOTAL:	TONS LS \$6,345.00



Proposal

(770) 927-0413 Office (770) 927-2533 Fax 1505 Dunlap Road, Luthersville, GA 30251 www.crawfordgrading.com

A	1	itted	triple
20	nm	INCOM	0"

Joe Vidal

Date:

January 14, 2019

City of Hogansville

waterplant@cityofhogansville.com

Job Name	Job Location	Plan Information	
Gate Valve Installation	City of Hogansville	N/A	

SCOPE OF WORK

Description	Quantity	Unit of Measure
8" GATE VALVE INSTALLATION W/ BOX, PAD & POST	1	EA
1	TOTAL:	\$1,700.00
6" GATE VALVE INSTALLATION W/ BOX, PAD & POST	1	EA
	TOTAL:	\$1,300.00

PROJECT NOTES:

- 1) QUOTE FOR GATE VALVE INSTALLATION IS BASED ON INSTALLATION OF VALVE WHILE INSTALLING NEW FIRE HYDRANT ASSEMBLY UNDER THE PHASE 2 FIRE HYDRANT INSTALLATION QUOTE.
- 2) QUOTE IS NOT BASED UPON INSTALLING A SINGLE ISOLATED VALVE IN A NEW LOCATION.

Notes:

Price does not include permits, bonds, license, engineering, staking, surveying, silt fence, clearing, landscaping, pavement, testing, curb or sidewalk replacement <u>unless noted above</u>. Rock Excavation is \$60.00 per Cubic Yard. Minimum Rock Excavation Fee is \$2,500.00

This Proposal may be withdrawn if not accepted within 30 days. If any additional testing or any intermediate testing is required, then an additional fee will be charged.
To accept this quotation, sign here and return: